Abstract.

Items of work	Per	Rate	Quantity	Cost	Total
Earthwork excavation and foundation	C. yd.		70		
Concrete filling foundation	C. ft.		578		
Burnt brick in chunam foundation	,,		986		
Do basement	,,		655		
Do in mud superstructure	,,		1,519		
Do in chunam	,,		496		
Coping with burnt brick in chunam	R. ft.		42		
Burnt stone slabs dressed and fixed	S. ft.		297		
Burnt brick in chunam arch work	C. ft.		L. S.		
Teakwood battened doors complete	S. ft.		108		
Do pannelled doors	,,		86		
Honneywood work wrought and put up	C. ft.		66·6		
Cut stone pillars nicely dressed with base and capitals	Each		6		
Roofing with 1st class Mangalore tiles and teak reepers	Sq.		13·48		
Ridge tiles set in mortar	R. ft.		62		
Teakwood eave board ordinary	,,		157		
Constructing V-shaped and lead of drains lump sum	..		..		
Teakwood pannelled windows with glazed shutters and iron bars, etc.	S. ft.		61		
Do battened shutters windows	,,		42		
Zinc sheets for valley	,,		96		
Teakwood planks for valley	,,		96		
Plastering with chunam	Sq.		44·35		
White and colourwashing	,,		44·35		
Flooring with Mangalore tiles an 3" concrete and cement pointing	,,		2·30		
Flooring with Cuddapah slabs	,,		4·97		
Gravelling the compound	L. S.		..		
Chacolate painting	Sq.		5·94		
Constructing combined chimnies	L. S.		..		
Constructing seats in laterin stone flogging cement painting tarring 3' high and drainage pipe, etc., to laterine.	,,		..		
Tarring timber	,,		5		
Pestal and mortar	Each		..		
Iron hold ports	,,		96		
Cup board with pegs to supports wood oiling	Sq.		2·55		

K. V. KARVE,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF INDUSTRIES AND COMMERCE.

Dated 14th June 1920.

Notice is hereby given that sealed tenders will be received at the Office of the Director of Industries and Commerce, up to 15th July 1920, for the supply of Block tin. An approximate estimate of quantities is given below. These quantities are not guaranteed. The supply should be completed by the end of July 1920.

2. The tenders should be accompanied by a statement in the form given below, showing the rate at which the Material specified will be supplied for delivery at Government Metal Factory.

Description	Unit	Rate
One ton block tin.		

3. Each tender must be accompanied by a deposit of Rs. 200 (two hundred) in cash as earnest money, and be superscribed "Tender for the supply of Block tin," in default of which, tenders will be rejected.

4. The final acceptance of any tender will rest with the Director of Industries and Commerce, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

6. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Director's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

N. LAKSHMINARASIMHAIYA,
For *Director.*